


15-179-20499-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sheridan County, Sec. 24 Twp. 9 Rge. 27 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
C SE NW



Locate well correctly on above  
Section Plot

Lease Owner Bass Enterprises  
Lease Name Ziegler Well No. 1  
Office Address P. O. Box 2760, Midland, Texas 79702  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole  
Date Well completed 3/8/78 19  
Application for plugging filed 3/8/78 19  
Application for plugging approved 3/8/78 19  
Plugging commenced 3/8/78 19  
Plugging completed 3/8/78 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4455  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	259	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 1100' with 70 sacks 50/50 Poz 6% gel  
Middle plug at 240' with 20 sacks 50/50 Poz 6% gel  
Top & bridge at 40' with 10 sacks 50/50 Poz 6% gel  
2 sacks in rathole

RECEIVED  
CORPORATION COMMISSION  
MAR 21 1978  
03-21-1978  
CONSERVATION DIVISION  
Wichita, Kansas

Job complete 1:45 p. m. 3/8/78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of March, 1978

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Bass Enterprises  
P. O. Box 2760  
Midland, Texas 79702

LEASE: Ziegler No.1  
C SE NW Sec. 24-9S-27W  
Sheridan County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 2/25/78

COMPLETED: 3/8/78

RTD: 4455'

CASING: 8-5/8 set at 259' with 200 sacks cement

0' to 263' 12 1/4" Surface hole, Clay, Sand, Shale  
263' to 1935' Shale & Shells  
1935 to 2090' Sand  
2090' to 2300' Shale & Shells  
2300' to 2362' Anhydrite  
2362' to 2670' Shale & Shells  
2670' to 3220' Shale & Lime  
3220' to 3625' Lime & Shale  
3625' to 4062' Lime  
4062' to 4110' Lime & Shale  
4110' to 4325' Lime  
4325' to 4415' Lime & Shale  
4415' to 4455' Lime  
4455' RTD

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and accurate copy of the Ziegler No.1 log for Bass Enterprises.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this 20th day of March 1978.

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1981.

RECEIVED  
STATE DEPARTMENT OF REVENUE  
03-21-1978  
MAR 21 1978

