

15-179-20581-00-00

FORM CP-4


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sheridan County. Sec. 29 Twp. 9S Rge. 27W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NE SE NE

Lease Owner Suburban Propane Gas Corporation  
Lease Name KENNEDY #1 Well No. #1  
Office Address P.O. Box 17689, San Antonio, TX 78217  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed January 19 1981  
Application for plugging filed January 19 1981  
Application for plugging approved January 19 1981  
Plugging commenced January 19 1981  
Plugging completed January 19 1981  
Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4501'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. @ 4501'  
Set 1st Plug @ 1250' with 70 sx.  
Set 2nd Plug @ 260' with 20 sx.  
Set 3rd Plug @ 40' Solid Bridge with 10 sx.  
Rathole - 5 sx.  
50-50 posmix. 6% gel

Plug was down @ 11:45 a.m., 1/19/81  
State Plugger - Gilbert Balthazar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec./Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 1981

My commission expires 08-18-84

Jeanette A. Metheny  
Jeanette A. Metheny Notary Public.



JAN 26 1981  
01-26-1981

CONTRACTOR'S WELL LOG

15-179-20581-00-00

OPERATOR: Suburban Propane Gas Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: KENNEDY #1  
 LOCATION: NE SE NE, Section 29-9S-27W  
 Sheridan County, Kansas  
 SPUD DATE: 1/12/81  
 COMPLETION DATE: 1/19/81

0	2337	Sand & Shale
2337	2372	Anhydrite
2372	3662	Shale
3662	4028	Shale & Lime
4028	4322	Lime
4322	4505	Lime & Shale
	4505	

Spud hole @ 7:45 p.m., 1/12/81. Drilled 290' in a 12 1/4" hole. Ran 7 jts. of 8 5/8" - 23# casing (tally 281.67) Set @ 288' RTD. Cemented with 200 sx. of common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 12:30 a.m., 1/13/81. Cement by Allied Cementing.

T.D. @ 4501'. Set 1st Plug @ 1250' with 70 sx., Set 2nd Plug @ 260' with 20 sx., Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx., 50-50 posmix, 6% gel. Plug was down @ 11:45 a.m., 1/19/81. State Plugger - Gilbert Balthazar.

SAMPLE TOPS:

Anhydrite 2337'  
 B/Anhydrite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KENNEDY #1, NE SE NE, Section 29-9S-27W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of January, 1981.

Jeanette A. Metheny  
 Jeanette A. Metheny, Notary Public

JAN 26 1981  
 01-26-1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

