

15-179-20226-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 31 Twp. 9 Rge. 27W (E) (W)

Location as "NE/CNW%SW%" or footage from lines Approx. SW SW SW

Lease Owner Chief Drilling Co., Inc.

Lease Name Vickers Well No. #1

Office Address Suite 905 Century Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 8-23-69 19

Application for plugging filed 8-23-69 19

Application for plugging approved 8-23-69 19

Plugging commenced 8-23-69 19

Plugging completed 8-23-69 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4120 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	206'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1500' w/100 sacks cement
Plugged through drill pipe @ 210' w/40 sacks cement
Plugged through drill pipe @ 40' w/10sacks cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1969
CONSERVATION DIVISION
Wichita, Kansas
08-27-1969

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 1969

My commission expires May 9, 1971
Betty Brandt Notary Public.

15-179-20226-00-00

WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1969

CONSERVATION DIVISION
Wichita, Kansas

0827-1969

Chief Drilling Co., Inc.
905 Century Plaza
Wichita, Kansas 67202

#1 VICKERS
Approx. SW SW SW
Sec. 31-9-27W
Sheridan County

Contractor: Chief Drilling Co., Inc.

Commenced: 8-17-69
Completed: 8-23-69

Casing Record: Set 197' of 8 5/8" @ 206'
w/175 sacks Common Quickset.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & clay	0	1165	2714 Gr.
Shale, shells & sand strks.	1165	1286	2716 D.F.
Shale & sand	1286	1660	2719 K.B.
Shale, shells & sand strks.	1660	1930	
Sand	1930	2075	
Red bed & shale	2075	2245	
Red bed, shale & sand	2245	2290	
Anhydrite	2290	2325	
Shale & shells	2325	2414	
Shale & lime	2414	2760	
Shale & lime	2760	4050	
Lime	4050	4120	
T.D.	4120		

<u>FORMATION TOPS</u>	
Anhydrite	2290 + 429
Heebner	3826 -1107
Toronto	3848 -1129
Lansing	3864 -1145
T.D.	4120 -1401

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the approximate SW SW SW of Section 31-9-27W, Sheridan County, Kansas, to the best of my knowledge and belief.

Chief Drilling Co., Inc.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 26th day of August, 1969.

Betty Brandt
Betty Brandt, Notary Public

My Commission Expires:
May 9, 1971