

15-179-20336-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Sheridan County, Sec. 33 Twp. 9S Rge. (E) 27 (W)
Location as "NE/CNW/KSW" or footage from lines NE NW NW

Lease Owner Pate-Dombaugh, Inc.
Lease Name BERENS Well No. 1
Office Address 502 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7, 1972
Application for plugging filed (verbally) December 7, 1972
Application for plugging approved (verbally) December 7, 1972
Plugging commenced December 7, 1972
Plugging completed December 7, 1972
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 1275' w/70 sx.
2nd plug set at 245' w/20 sx.
3rd plug set at 40' w/10 sx.
Job completed at 3:00 a.m. 12-7-72.
State plugger: Bill Nichols

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1973
01-18-1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, SS.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1972

My commission expires February 10, 1975

Beverly Mann
Notary Public.

CONTRACTOR'S WELL LOG

15-179-20336-00-00

OPERATOR:	Pate-Dombaugh, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BERENS #1
LOCATION:	NE NW NW, Sec. 33-9S-27W Sheridan County, Kansas
GEOLOGIST:	Raymond Dombaugh
SPUD DATE:	November 26, 1972
COMPLETION DATE:	December 7, 1972

0	190	Clay - Sand
190	900	Shale
900	1450	Shale & Sheels
1450	1550	Sand
1550	1936	Shale
1936	2072	Sand
2072	2305	Shale
2305	2340	Anhydrite
2340	2815	Shale
2815	2990	Shale & Lime
2990	3636	Lime & Shale
3636	3795	Lime
3795	3898	Lime & Shale
3898	4100	Lime
	4100	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1973
 01-18-7973
 CONSERVATION DIVISION
 Wichita, Kansas

Drilled 231' of 12½" surface hole. Set 8-5/8", 24#, surface csg. at 229' K.B. w/150 sx. Portland cement, 3% Ca.Cl. and 2% gel. Plug was down at 7:00 p.m. 11-26-72. Dry and Abandoned

<u>SAMPLE TOPS</u>		<u>ELEVATION</u>
Anhydrite	2305 (+ 414)	2719 K.B.
B/Anhydrite	2340 (+ 379)	2717 D.F.
Heebner	3828 (-1109)	2711 G.L.
Toronto	3853 (-1134)	
Lansing	3868 (-1149)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BERENS #1, NE NW NW, Section 33-9S-27W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 8th day of December, 1972.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:
 February 10, 1975