

STATE OF KANSAS
CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

30235-00-0003
15-163-30325-00-00
API NUMBER Dec. 19, 1966

LEASE NAME Oswald
WELL NUMBER #3
SPOT LOCATION NW NW SE
SEC. 10 TWP. 9 RGE. 17 (E) or (W)
COUNTY Rooks
Date Well Completed 12-19-66
Plugging Commenced 7-13-84
Plugging Completed 7-16-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oil Property Management
ADDRESS 221 N. Main Suite 200 Wichita, Ks. 67202
PHONE # (316) 262-0841 OPERATORS LICENSE NO. 5247

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6 Hays Ks. (Carl Goodrow)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3461' bottom 3466' T.D. 3479'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3479'	3416'	4 1/2"	3470'	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 20 sacks cement & 1/2 sack of hulls spotted on bottom 2916' to 2500'. Spotted 1 sack hulls & 9 sacks gel. 2500' to 1213' 1 sack hulls & 60 sacks cement. Pumped 5 sacks cement in casing filled to the top. Pumped 35 sacks cement, 1 sack hulls, 8 sacks gel into 8 5/8" casing. Pressure holding at 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Superior Well Service License No. 7733
Address Box 276 Plainville, Ks.

STATE OF Kansas COUNTY OF Rooks, ss.

W.H. Peachee (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says:
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) W.H. Peachee
W.H. Peachee-President
(Address) 221 N. Main-Suite 200

SUBSCRIBED AND SWORN TO before me this 20 day of July, 1984
Wichita, Ks. 67202

Edna R. Peachee
Notary Public

My Commission expires: April 26, 1985

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1984
7/25/84
CONSERVATION DIVISION
Wichita, Kansas

15-163-30235-00-00
D & D DRILLING COMPANY, INC.

SCHWEITER BUILDING
WICHITA, KANSAS 67202
PHONE AM 5-0614

RECEIVED
STATE CORPORATION COMMISSION
7/17/84 JUL 17 1984
JAMES R. DANIELS
CONSERVATION DIVISION
Wichita, Kansas

GLENN M. DUNNE, JR.

ROTARY DRILLING LOG

OPERATOR: Oil Property Management ELEVATION: 2031 K.B.
CONTRACTOR: D & D Drilling Co., Inc. COMMENCED: 12/12/66
WELL: Oswald No. 3 COMPLETED: 12/19/66
LOCATION: NW NW SE Section 10-9S-17W
COUNTY: Rooks County, Kansas

Formations	Depth	Remarks
Shale	760'	Ran 2 jts. 8-5/8" surface
Shale and Sand	1303'	pipe at 77'. Cemented
Anhydrite	1340'	w/75 sx. HA5
Shale	1775'	
Shale and Lime	2417'	
Shale	2530'	
Shale and Lime	3005'	
Lime	3479'	
Rotary Total Depth	3479'	Set 4 1/2" casing @ 3470', 9' off bottom, w/200 sx. sat. salt pozmix, 3/4% CFR2.

A F F I D A V I T

State of Kansas)
) SS:
County of Sedgwick)

I, Colleen Chapple, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath state that the above drilling log is true and correct to the best of my knowledge and belief.

Colleen Chapple

Colleen Chapple

Subscribed and sworn to before me this 20th day of December, 1966.

My Commission Expires:
November 9, 1969

Marilyn E. Fox

Marilyn E. Fox, Notary Public

STATE
STATE
STATE