


STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 211 No. Broadway  
 Wichita, Kansas

R 15-163-02809-00-01 KCC  
 WELL PLUGGING RECORD  
 GS

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 9 Twp. 9 Rge. 17 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines NE NE SW  
 Lease Owner Morgenstern & Specter, Inc.  
 Lease Name Fike Well No. 2  
 Office Address Russell, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) oil  
 Date well completed April 13, 1958 19\_\_\_\_  
 Application for plugging filed 12-25-61 19\_\_\_\_  
 Application for plugging approved 12-27-61 19\_\_\_\_  
 Plugging commenced 2-23-62 19\_\_\_\_  
 Plugging completed 2-27-62 19\_\_\_\_  
 Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation arbuttle Depth to top 3484 Bottom 3498 Total Depth of Well 3501 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	279'	None
				4-1/2"	3496'	2286

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3501', sanded to 3480' and dumped 3 sacks of cement @ 3480' with dump bailer. Pulled 4 1/2" casing to 550' and circulated pipe with 25 sacks of jell mud @ 550' and pumped in 20 sacks of cement. Pulled 4 1/2" casing to 170', and pumped in 20 sacks of cement. Pulled balance of 4 1/2" casing and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

3/15/62  
**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAR 19 1962  
 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
 Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1962

My commission expires May 20, 1964 Milton J. Volin Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


**COPY**  
R. 17W

Company. PETROLEUM, INCORPORATED.  
Farm. Fike No. 1

SEC. 9 T. 9 R. 17W  
NE NE SW

Total Depth. 3501'  
Comm. 4-3-58 Comp. 4-13-58  
Shot or Treated.  
Contractor. Garvey Drilling Co.,  
Issued. 12-6-58

County Rocks.  
KANSAS



**CASING:**  
8 5/8" O 279' W/150 sks. cem.,

Elevation. 2059' DE.

Production. Dry.,

Figures indicate Bottom of Formations.

Post Rock	40
shale & clay	200
shale	850
sand	1050
red bed & shale	1180
shale & shells	1340
Anhydrite	1385
shale & shells	1855
shale	2040
shale & shells	2150
lime & shale	2560
lime	2675
lime & shale	2845
lime	3501
Total Depth.	

**TOPS SCOUT:**

Anhydrite	1340
Topeka	2940
Heebner	3163
Toronto	3187
Lansing	3206
Base/Kansas City	3396
Marmaton	3427
Basal Pennsylvania Sand	3456
Arbuckle	3484

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 27 1961

CONSERVATION DIVISION  
Wichita, Kansas

12/27/61