

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

#4

API NUMBER 15-179-20,925-00-00

LEASE NAME Pratt

WELL NUMBER 1

4340 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 4 TWP. 9S RGE. 28 ~~XKEXXX(W)~~

COUNTY Sheridan

Date Well Completed 6-12-88

Plugging Commenced 6-13-88

Plugging Completed 6-13-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hinkle Oil Company

ADDRESS 1016 Union Center, Wichita, KS 67202

PHONE#(316) 267-0231 OPERATORS LICENSE NO. 5290

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays District Carl Goodrow, State Plugger

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
					292.90	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump heavy mud to 2300'. 1st plug from 2300' to 2200' w/25 sx. Pump mud to 1325', 2nd plug from 1325' to 925' w/100 sx. and 1 sx. hulls. Pump mud to 350', 3rd plug from 350' to 190' w/40 sx. Pump mud to 40', 4th plug from 40' to surface w/wider plug and 10 sx. cement. 15 sx. in rathole. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 801 Union Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 88

Janet A. Stuck
Notary Public

My Commission Expires: 12-29-90



RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1988
06-21-1988