

15-065-02487-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 1 Twp. 10 Rge. 21 (NW 1/4 NE 1/4 SE 1/4)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines

Lease Owner: D. G. Hansen

Lease Name: Muilenberg Well No. 2

Office Address: Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: July 2- 1949 19

Application for plugging filed: July 2- 1949 19

Application for plugging approved: July 2- 1949 19

Plugging commenced: July 3- 1949 19

Plugging completed: July 3- 1949 19

Reason for abandonment of well or producing formation:

If a producing well is abandoned, date of last production: 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: C. D. Stough, Great Bend, Kansas

Producing formation: Depth to top: Bottom: Total Depth of Well: 3974 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Clay and Sand		0	40			
Shale & Shells		40	198	8 5/8"	192'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with heavy mud from total depth to 190' and permanent plug placed at 190 feet and cemented with 15 sacks of cement. Then heavy mud to bottom of 30 feet and permanent plug placed at that depth and cemented 10 sacks from 30' to bottom of cellar.

RECEIVED
JUL 9 1949

D. G. Hansen, Contractor
By _____

07-21-1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: D. G. Hansen, Logan, Kansas.

STATE OF ~~Barton~~ Kansas, COUNTY OF Barton, ss. Jim Adkins, contractor (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

1502 12th St., Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of July 19 49

Caroline B. Adkins Notary Public.

My commission expires 1-26-1952

22-2625 2-48-15M


PLUGGING
WELL SEC 1 T 10 R 21
BOOK PAGE 104 LINE 13

15-065-02487-00-06

DRILLERS LOG

D. G. Hansen-Muilenburg #2-NW NE SE, Section 1-10s-21w, Graham County,
Kansas

0'	-	40'	Clay and Sand
40'	-	198'	Shale and Shells
198'	-	240'	Shale
240'	-	315'	Kaleechee
315'	-	400'	Shale and Shells
400'	-	740'	Shale
740'	-	980'	Shale and Sand
980'	-	1080'	Sand
1080'	-	1275'	Sand and Shale
1275'	-	1465'	Sand
1465'	-	1770'	Shale
1770'	-	1805'	Anhydrite
1805'	-	2235'	Shale and Shells
2235'	-	2345'	Shale and Lime
2345'	-	2525'	Lime
2525'	-	2635'	Lime and Shale
2635'	-	2810'	Lime
2810'	-	3565'	Lime and Shale
3565'	-	3755'	Lime
3755'	-	3790'	Lime and Shale
3790'	-	3971'	Conglomerate
3971'	-	3974'	Lime
TD	-	3972'	



RECORDED

07-21-1949

APR 21 1949

STATE OF KANSAS

COMMISSIONER OF GEOL.