

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bear Petroleum, Inc.
Address: P.O. Box 438, Haysville, KS 67060
Phone: (316) 524-1225 Operator License #: 4419
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-5-07 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 3794 Bottom: 3814 T.D. 3920

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-20281-00-01
Lease Name: Kraemer OWWD
Well Number: #1
Spot Location (QQQQ): C - NW - NW
4617 Feet from North / South Section Line
4570 Feet from East / West Section Line
Sec. 11 Twp. 11 S. R. 22 East West
County: Trego
Date Well Completed: 11-9-83
Plugging Commenced: 11-5-07
Plugging Completed: 11-6-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	218	8 5/8"	218	0
	Production	Surface	3919	4 1/2"	3919	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran pipe to 3501' and dumped 50 sacks cement. Pulled tubing to 3000' and dumped 10 sacks cement. Pulled tubing to 1500' and circulate 150 sacks cement to surface. Pulled tubing out of hole. Squeezed 4 1/2" casing with 20 sacks cement. Squeezed braden head with 25 sacks cement. Job Complete.

Total cement - 255 sacks 60/40 4% gel

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Gaschier Pulling Service, Inc. License #. 33137

DEC 12 2007

Address: P.O. Box 21, Ellis, KS 67637

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County, Sedgwick, ss.

R. A. Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

(Signature) _____

(Address) P.O. Box 438, Haysville, KS 67060

SUBSCRIBED and SWORN TO before me this 30th day of November, 20 07

SHANNON HOWLAND
Notary Public - State of Kansas
My Appt. Expires 3/10/08

Shannon Howland
Notary Public

My Commission Expires: 3/10/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]