

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: C&K Oil  
Address: POB 531, Claflin, KS 67525  
Phone: (620) 786-8744 Operator License #: 31561  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11/11/07 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3376 Bottom: \_\_\_\_\_ T.D. 3380  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-21577-00-00  
Lease Name: Maes  
Well Number: 1  
Spot Location (QQQQ): W/2 - NE - NW - SE  
2310 Feet from  North /  South Section Line  
1815 Feet from  East /  West Section Line  
Sec. 9 Twp. 16 S. R. 13  East  West  
County: Barton  
Date Well Completed: 11/19/79  
Plugging Commenced: 11/12/07  
Plugging Completed: 11/12/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil	3376	T.D.	8 5/8"	309'	none
				5 1/2"	3378	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 3300' spotted 25 sax 60/40 4% Gel w/ 100# hulls. Pulled tubing up to 3065' and spotted 15 sax gel w/ 150# hulls. Pull tubing up to 1600' and mix cement and circulate to surface w/ 230 sax and 700# hulls. Pull tubing. Tie onto Braden Head and squeeze w/ 35 sax cement to 400#. Top off casing w/ 40 sax cement. Job complete.

Name of Plugging Contractor: Classic Well Service, Inc. License #: 32098  
Address: POB 539, Claflin, KS 67525

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 12 2007  
CONSERVATION DIVISION  
WICHITA KS

Name of Party Responsible for Plugging Fees: C&K Oil  
State of Kansas County, Barton, ss.  
Chris Hoffman

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Chris Hoffman  
(Address) C&K Oil, POB 531, Claflin, KS 67525

SUBSCRIBED and SWORN TO before me this 11th day of December, 20 07  
Bonnie Jeffrey My Commission Expires: 9/20/2010  
Notary Public  
State of Kansas  
Notary Public  
My Commission Expires  
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*

