

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
Phone: (303) 893-5090 Operator License #: 33476
Type of Well: D&A Docket #:
The plugging proposal was approved on: 11/2/2007
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-109-20790-0000
Lease Name: Council
Well Number: 1D-17-1135
Spot Location (QQQQ): - E2 - E2 - NE
1320 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 17 Twp. 11 S. R. 35 East West
County: Logan
Date Well Completed:
Plugging Commenced: 11/05/2007
Plugging Completed: 11/05/2007

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 357' surface 8-5/8" 10/27/2007

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

- Plug #1 @ 2710' w/ 25 sk 60/40 A Pozmix w/ 4% gel & 0.25 pps Flocele. Wt: 12.5 pps. Yield: 1.40ft3/sk.
Plug #2 @ 1700' w/ 100 sk 60/40 A Pozmix w/ 4% gel & 0.25 pps Flocele. Wt: 12.5 pps. Yield: 1.40ft3/sk.
Plug #3 @ 425' w/ 40 sk 60/40 A Pozmix w/ 4% gel & 0.25 pps Flocele. Wt: 12.5 pps. Yield: 1.40ft3/sk.
Plug #4 @ 40' w/ 100 sk 60/40 A Pozmix w/ 4% gel & 0.25 pps Flocele. Wt: 12.5 pps. Yield: 1.40ft3/sk. Rat hole: 15 sx. Mouse hole 10 sx.

Name of Plugging Contractor: Allied Cementing Company License #: 115725 99996
Address: P.O. Box 31 Russell, KS RECEIVED KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC DEC 12 2007
State of Colorado County, Denver, ss. CONSERVATION DIVISION WICHITA, KS

Cassandra Parks (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) 410 17th St. Suite 900 Denver CO 80202

SUBSCRIBED and SWORN TO before me this 6 day of December, 2007
Elaine Nitch Notary Public My Commission Expires: 5/5/2009