

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shelby Resources, LLC
Address: P.O. Box 1213, Hays, Kansas 67601
Phone: (785) 623-3290 Operator License #: 31725
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-09-2007 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2871 Bottom: 3108 T.D. _____
Lansing Depth to Top: 3198 Bottom: 3404 T.D. _____
Arbuckle Depth to Top: 3417 Bottom: 3550 T.D. 3550

API Number: 15-009-25119-0000
Lease Name: Hoffman Ranch
Well Number: #1-20
Spot Location (QQQQ): app. - SW - NW - NW
1040 Feet from North / South Section Line
220 Feet from East / West Section Line
Sec. 20 Twp. 17 S. R. 13 East West
County: Barton
Date Well Completed: 11-10-2007
Plugging Commenced: 11-10-2007
Plugging Completed: 11-10-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		000	920' KB	8-5/8"	908'	none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Heavy mud in the hole. Bottom plug was @ 3400' with 25 sxs., 950' with 50 sxs., 450' with 75 sxs., and 40' with 10 sxs. Also plugged rat hole with 15 sxs.
Allied Cementing (ticket #25421) cemented with a total of 175 sxs. of 60/40 poz with 4% gel. Sterling Drilling reported this to KCC on 11-13-2007.

Name of Plugging Contractor: STERLING DRILLING COMPANY License #: 5142 RECEIVED KANSAS CORPORATION COMMISSION
Address: P.O. Box 31, Russell, Kansas 67665 DEC 13 2007

Name of Party Responsible for Plugging Fees: Shelby Resources, LLC
State of Kansas County, Ellis, ss. _____
Brian Karlin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brian Karlin
(Address) P.O. Box 1213, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 10th day of December, 20 07
Stale D Fischer My Commission Expires: 6-18-2011
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]