

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shelby Resources, LLC
Address: P.O. Box 1213, Hays, Kansas 67601
Phone: (785) 623 - 3290 Operator License #: 31725
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-22-2007 (Date)
by: Lin Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3784 Bottom: 4200 T.D. _____
Viola Depth to Top: 4326 Bottom: 4465 T.D. _____
Arbuckle Depth to Top: 4585 Bottom: 4640 T.D. 4640

API Number: 15 - 007-23169-0000
Lease Name: Thompson Trust
Well Number: #2-8
Spot Location (QQQQ): app. - SE - NW - SW
1736 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 8 Twp. 31 S. R. 14 East West
County: Barber
Date Well Completed: 8-25-2007
Plugging Commenced: 8-25-2007
Plugging Completed: 8-25-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		000	65' KB	20"	56'	none
		000	1123' KB	8-5/8"	1111'	none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Heavy mud in the hole. Plugged well with 50 sxs. @ 4585', 50 sxs. @ 1140', 40 sxs. @ 600', and 20 sxs. @ 60'. Also put 15 sxs. in rathole and 10 sxs. in mousehole. Allied Cementing (ticket #32544) used a total of 185 sxs. of 60/40 poz with 6% gel. Sterling Drilling Company reported plugging to KCC on 8-27-2007.

Name of Plugging Contractor: sterling Drilling Company License #: 5142
Allied Cementing Company
Address: P.O. Box 31, Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: Shelby Resources, LLC
State of Kansas County, Ellis, ss.
Brian Karlin
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brian Karlin
(Address) P.O. Box 1213, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 10th day of December, 20 07
Gale D. Fischer My Commission Expires: 6-18-2011
Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]