

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shelby Resources, LLC
Address: P.O. Box 1213, Hays, Kansas 67601
Phone: (785) 623-3290 Operator License #: 31725
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-28-2007 (Date)
by: Lin Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3614 Bottom: 3973 T.D. _____
Mississippi Depth to Top: 4052 Bottom: 4114 T.D. _____
Arbuckle Depth to Top: 4425 Bottom: 4500 T.D. 4500

API Number: 15-185-23432-0000
Lease Name: Schmisseur Farms
Well Number: #1-35
Spot Location (QQQQ): app. - N/2 - SE -
1879' Feet from North / South Section Line
1350' Feet from East / West Section Line
Sec. 35 Twp. 27 S. R. 12 East West
County: Pratt
Date Well Completed: 6-29-2007
Plugging Commenced: 6-29-2007
Plugging Completed: 6-29-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		000	222'	13-3/8"	222'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Heavy mud in hole. Bottom plug @ 4410' with 50 sxs. Put 2nd plug @ 600' with 80 sxs. The 3rd plug @ 240' with 100 sxs. The top plug @ 60' used 40 sxs. and cemented to surface. Basic Energy cemented with 60/40 poz with 6% gel and 1/4# Floseal. Plugged rathole with 15 sxs. and mousehole with 10 sxs. Plug down on 6-29-2007. Sterling Drilling reported to KCC on 6-29-2007.

KCC Pkt per CP 2/3

Name of Plugging Contractor: Basic Energy Sterling Drilling Company License #: 5142
Address: 10244 NE Hiway 61, P.O. Box 8613, Pratt, Kansas 67124-8613

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 13 2007


Name of Party Responsible for Plugging Fees: Shelby Resources, LLC
State of Kansas County, Ellis, ss.

CONSERVATION DIVISION
WICHITA, KS

Brian Karlin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brian Karlin
(Address) P.O. Box 1213, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 10th day of December, 20 07
Gale D. Fischer My Commission Expires: 6-18-2011
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pkt