

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

051-19184-00-00

Lease Operator: T.D. ^I Oil Operations
 Address: 1310 Bison Road Hays, Kansas 67601
 Phone: (785) 628-2593 Operator License #: 4787
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 12-3-07 (Date)
 by: Herb Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Toronto Depth to Top: 3084' Bottom: 3091 T.D. _____
LKC Depth to Top: 3114 Bottom: 3310 T.D. _____
Arbuckle Depth to Top: 3399' Bottom: _____ T.D. 3401

API Number: 15 - (7-14-50)
 Lease Name: Dreiling "C"
 Well Number: 12
 Spot Location (QQQQ): NW - NW - SW -
2970 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 22 Twp. 14 S. R. 16 East West
 County: Ellis
 Date Well Completed: 7-14-50
 Plugging Commenced: 12-06-07
 Plugging Completed: 12-06-07

KCC PPT
Per Operator
Terry

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Toronto	Water	3087'	3091'	8 5/6"	722'	None
LKC	Oil and Water	3111'	3300'	5 1/2"	3399'	None
Arbuckle	Oil and water	3399'	3401'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied to 5 1/2" Casing and mixed 100 sxs. 60/40 Poz Mix with 4% Gel. with 400# Hulls. Followed with 19 sxs. Gel with 200# Hulls. Followed with 120 sxs. 60/40 Poz Mix with 4% Gel- 5 1/2" on vacuum. Tied to 8 5/8" Casing and mixed 5 Sxs. 60/40 Poz Mix with 4% Gel and pressured to 200# and shut in. Let 5 1/2" Casing set 45 minutes. Fluid appeared to be 500' from surface. Began Trickling 60/40 Poz Mix with 4% Gel down the 5 1/2" Casing. Got 55 sxs. in and stayed at surface. Job Complete. Marvin Mills with KCC as witness.

Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99996
 Address: Russell, Kansas


Name of Party Responsible for Plugging Fees: T.D. ^I Oil Operations
 State of Kansas County, Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W. Piesker
 (Address) P.O. Box 177 Victoria, Kansas 67671

SUBSCRIBED and SWORN TO before me this 6TH day of DECEMBER 2007
Patricia Dreiling My Commission Expires _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC PPT
RECEIVED
DEC 17 2007
CONSERVATION DIVISION
WICHITA, KS

PPT

ALLIED CEMENTING CO., INC. 30540

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Great Bend

DATE <u>12-6-07</u>	SEC. <u>22</u>	TWP. <u>14</u>	RANGE <u>16</u>	CALLED OUT <u>7:00AM</u>	ON LOCATION <u>9:30AM</u>	JOB START <u>10:30AM</u>	JOB FINISH <u>12:30PM</u>
LEASE <u>Bringing</u>	WELL # <u>2</u>		LOCATION <u>I-20 & Welch Exit 2 1/2 S,</u>		COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one) <u>OLD</u>				<u>1w, 1/2 S W/into</u>			

CONTRACTOR _____ OWNER Same

TYPE OF JOB Plug to Abandon

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 250# MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT AMOUNT ORDERED 280 cu 6 1/4 490 cu 1 1/2

19 cu 800# Hulls

COMMON	<u>168 cu</u>	@	<u>11.10</u>	<u>1864.80</u>
POZMIX	<u>112 cu</u>	@	<u>6.20</u>	<u>694.40</u>
GEL	<u>29 cu</u>	@	<u>16.15</u>	<u>468.35</u>
CHLORIDE		@		
ASC		@		
<u>Hulls 800#</u>		@	<u>25.50</u>	<u>204.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>317 cu</u>	@	<u>1.90</u>	<u>602.30</u>
MILEAGE	<u>317 cu 09</u>	@	<u>16</u>	<u>456.48</u>
TOTAL				<u>4304.83</u>

EQUIPMENT

PUMP TRUCK CEMENTER Terry D

120 HELPER Dwayne W

BULK TRUCK _____

362 DRIVER Robert Y.

BULK TRUCK _____

_____ DRIVER _____

REMARKS:

Hooded to 5 1/2" cas. Mixed 100 cu 6 1/4
4 1/2 cu 1 1/2" 400# Hulls - 19 cu 1 1/2" 500#
w/200# Hulls - 12 cu 6 1/4 490 cu 1 1/2
Pressure. Hooded to Annular. Mixed 5 cu
6 1/4 4 1/2 cu 1 1/2" & Pressure to 250#, Wanted
45 minutes. Filled 5 1/2" cas w/ 5 cu 200#
Hulls.

Thanks
5

CHARGE TO: TDI

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 720.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 16 @ 6.00 96.00

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 816.00

RECEIVED PLUG & FLOAT EQUIPMENT
KANSAS CORPORATION COMMISSION

DEC 17 2007 _____ @ _____

_____ @ _____

CONSERVATION DIVISION _____ @ _____

WICHITA KS _____ @ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Terry W. Peisker

PRINTED NAME _____