

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-00800-00-00

API NUMBER Spud 3/4/59

LEASE NAME Wheeler

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 8 TWP. 10 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 3/13/59

Plugging Commenced 9:00 A.M. 10/26/92

Plugging Completed 10:15 A.M. 10/26/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 26, 1992 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	186'	None
				5 1/2"	3875'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Down 5 1/2" csg. at 600# Max Pressure, mixed 500# hulls with
325 sx cement, and shut in at 300#. Checked 8 5/8" csg.,
it is full of cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P. O. Box 31, Russell, Kansas 67665 RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust NOV 19 1992

STATE OF KANSAS COUNTY OF PHILLIPS, ss. 11-19-1992

Dane G. Bales, Manager (Employee of Operator) or Operator of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Dane G. Bales*

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 18 day of November, 1992



Betty Jane Bittel
Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1996.

15-065-00800-00-00

WELL LOG

OPERATOR D. G. Hansen SEC. 8-10-21W
 WELL NAME Wheeler #1 LOC. SW SW SW
 TOTAL DEPTH 3900' COUNTY Graham
 COMM. March 3, 1959 COMP. March 13, 1959 STATE Kansas
 RIG NO. 1 ELEVATION 2292' K.B.
 CASING: Ran 186.25' (9 jts.) 8-5/8" OD Surface Casing. PRODUCTION: Producing
 Set 5-1/2" OD Casing @3875' (119 jts.)

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	715	Sand-Shale		
715	1000	Shale-Sand		
1000	1300	Sand		
1300	1779	Red Bed		
1779	1818	Anhydrite		
1818	2515	Shale-Shell	0° - 2500	
2515	2675	Shale-Lime		
2675	2990	Lime-Shale	0° - 2750	
2990	3115	Shale-Lime	0° - 3000	
3115	3220	Lime-Shale		
3220	3460	Lime	0° - 3250	
3460	3550	Lime-Shale		
3550	3582	Lime		DST 3564-3582'
3582	3628	Lime-Shale		DST 3607-3628'
3628	3720	Lime		
3720	3745	Lime-Shale		DST 3728-3745'
3745	3840	Lime		DST 3824-3835'
3840	3900	Lime-Shale		DST 3894-3900'

RECEIVED

MAR 18 1959

D. G. HANSEN

Time.....

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 17th day of March, 1959.

My commission expires:
 May 20, 1959

Vicky Jacobs
 Vicky Jacobs - Notary public



RECEIVED
 STATE CORPORATION COMMISSION
 07-30-1992
 JUL 30 1992
 CONSERVATION DIVISION
 Wichita, Kansas