

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21519-00-00
Spot: SUNWASE Sec/Twnshp/Rge: 8-23S-13E
950 feet from S Section Line, 1160 feet from E Section Line
Lease Name: HARSHMAN Well #: 1
County: GREENWOOD Total Vertical Depth: 1878 feet

Operator License No.: 6078
Op Name: EVANS OIL INC.
Address: PO BOX 67
LEBO, KS 66856

String	Size	Depth (ft)	Pulled (ft)	Comment
STRL	4.5	1878	0	
SURF	8.5	86	0	

61.04

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2007 9:00 AM
Plug Co. License No.: 6470 Plug Co. Name: SCHANKIE WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 1700', 50' cement plug @ 800', 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2007 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700' pumped 20 sxs cement, pulled tubing to 780' shot casing @ 800', pumped 25 sxs cement, pulled tubing to 160' shot casing @ 165', pumped 45 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1803	1808		

RECEIVED
KCC DISTRICT #3

NOV 26 2007 MH

CHANUTE, KS

INVOICED

DATE 12/19/07
INV. NO. 2008060928

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 06 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

PH