

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-22421-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 8-23S-13E  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HARSCHMAN FARMS TWIN Well #: 6  
County: GREENWOOD Total Vertical Depth: 1831 feet

Operator License No.: 6078  
Op Name: EVANS OIL INC.  
Address: PO BOX 67  
LEBO, KS 66856

String	Size	Depth (ft)	Pulled (ft)	Comment
STRL	4.5	1831	0	
SURF	8.5	150	0	59.51

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2007 9:00 AM  
Plug Co. License No.: 6470 Plug Co. Name: SCHANKIE WELL SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' cement plug @ 1700' 50' cement plug @ 800' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/08/2007 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700' pumped 20 sxs cement, pulled tubing to 780', shot casing @ 800' pumped 25 sxs cement, pulled tubing to 150', shot casing @ 165', pumped 75 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED  
KCC DISTRICT #3  
NOV 26 2007 MH  
CHANUTE, KS

INVOICED  
DATE 12/19/07  
INV. NO. 2008060928

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 06 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:  
Plugged through: TBG

District: 03 Signed Mike Heffern (TECHNICIAN)

*PH*