

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-22453-00-00
Spot: SESWSE Sec/Twnshp/Rge: 8-23S-13E
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HARSCHMAN FARMS Well #: 9
County: GREENWOOD Total Vertical Depth: 1816 feet

Operator License No.: 6078
Op Name: EVANS OIL INC.
Address: PO BOX 67
LEBO, KS 66856

String	Size	Depth (ft)	Pulled (ft)	Comment
<i>Prod</i> STRE	4.5	1816	0	
SURF	8.5	150	0	<u>59.02</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2007 9:00 AM
Plug Co. License No.: 6470 Plug Co. Name: SCHANKIE WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 1700' 50' cement plug @ 800' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN
Date/Time Plugging Completed: 11/09/2007 3:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700' pumped 20 sxs cement ,pulled tubing to 780',shot casing @ 800' pumped 25 sxs cement , pulled tubing to 150' shot casing @ 165' pumped 75 sxs cement to surface,gel spacers between cement plugs.

RECEIVED
KCC DISTRICT #3
NOV 26 2007 *MH*
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1796	1802		
INVOICED			
DATE <u>12/19/07</u>			
INV. NO. <u>2008060928</u>			

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 06 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed *Mike Heffern*
(TECHNICIAN)