

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00368-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 8-8S-23W
4956 feet from S Section Line, 2239 feet from E Section Line
Lease Name: MONTGOMERY AREA SWD Well #: 1
County: GRAHAM Total Vertical Depth: 1885 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		1495		
PROD	4.5	1885	0	500 SX
SURF	8.625	165	0	100 SX
T1	2.375	1495		

Well Type: SWD UIC Docket No: D20929.0 Date/Time to Plug: 11/09/2007 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Order 125 sxs 60/40 pozmix - 4% gel and hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/12/2007 12:15 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Ran tubing to 1650' - pumped 50 sxs cement with hulls.
Pulled tubing to 800' - pumped 65 sxs cement with hulls.
Pulled tubing and tied onto production casing - pumped 15 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.
Tied onto annulus and pumped 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
1600	1630		

INVOICED
DATE 12-19-07
INV. NO. 2008060944

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 12 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

Form CP-2/3

DEC 11 2007

