

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20350-00-01
Spot: SESENW Sec/Twnshp/Rge: 24-30S-42W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SMITH Well #: 1
County: STANTON Total Vertical Depth: 5650 feet

Operator License No.: 32628
Op Name: QUANTUM OPERATING COMPANY
Address: 7860 E BERRY PL SUITE 120
GREENWOOD VILLAGE, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5550		
PROD	5.5	5646	1560	WITH 235 SX CMT <u>183.63</u>
SURF	8.625	1506		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/30/2007 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SET A CIBP & PLACE 2 SX CMT OR A 30 SX PLUG AT 5100'. PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 11/30/2007 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PUMPED 30 SX CMT AT 5100'. 1ST PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5554	5558		
5174	5190		

INVOICED
DATE 12-19-07
INV. NO. 2008060943

RECEIVED
KANSAS CORPORATION COMMISSION


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: TBG

DEC 11 2007

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed _____

Steve Durrant

(TECHNICIAN)

Form CP-2/3

PKF