

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20992-00-01
Spot: E2SESWSW Sec/Twnshp/Rge: 2-12S-22W
330 feet from S Section Line, 4110 feet from E Section Line
Lease Name: HUFFMAN Well #: 3
County: TREGO Total Vertical Depth: 4190 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4128	0	w/150 sxs cmt
SURF	8.625	217	0	w/175 sxs cmt

136.18

Well Type: SWD UIC Docket No: D21084.0 Date/Time to Plug: 12/07/2007 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 405 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tubing stuck in the hole at 2772'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2007 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing into 2490' - pumped 110 sxs cement with 250# hulls.
Pulled tubing to 1350' - pumped 35 sxs cement with 150# hulls - cement circulated.
Pulled tubing out - tied onto the 4 1/2" - squeezed with 20 sxs cement and 100# hulls.
S.I.P. 350#.
Tied onto backside - pumped 30 sxs cement with 100# hulls. Full.

Perfs:

INVOICED
DATE 12-19-07
INV. NO. 2008060944

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 12 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #28849.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

Form CP-2/3

DEC 10 2007

ppg

A. SCOTT RITCHIE
 125 N. MARKET, #950 #3 HUFFMAN 2-12-22W
 WICHITA, KS 67202 150' W.
 CONTR MURFIN DRLG. CO. CTY TREGO C S/2 S/2 SW

GEOL _____ FIELD SHAW CREEK SOUTH
 E 2379 KB CM 5/4/82 CARD ISSUED 8/19/82 IP SWDW
 API 15-195-20,992 ARB OH 4128-4190

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1818	+ 561
B ANH		1863	+ 516
TOP		3414	-1035
HEEB		3629	-1250
TOR		3651	-1272
LANS		3665	-1286
B KC		3912	-1533
MARM		3987	-1608
*ARB		4103	-1724
LTD		4089	-1710
RTD		4190	-1811
*SMP TOP			

8-5/8" 217/175sx, 4 1/2" 4128/150sx
 DST (1) 3626-3685/30-45-30-45, 45' M,
 SSO, SIP 415-382#, FP 44-55/
 55-55#
 DST (2) 3692-3738/30-30-30-30, 278'
 SO&GCMW, SIP 502-480#, FP 65-98/
 120-148#
 DST (3) 3731-3753/30-30-30-30, 154'
 MW, SIP 855-844#, FP 33-44/55-76#
 DST (4) 3789-3870/30-45-30-45, 15' M,
 NSO, SIP 1172-1118#, FP 55-55/
 65-65#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)