

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21131-00-01  
Spot: SENW Sec/Twnshp/Rge: 2-12S-25W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: ZIEGLER OWWO Well #: 1-2  
County: TREGO Total Vertical Depth: 4210 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4209	0	w/200 sxs cmt
SURF	8.625	327	0	w/140 sxs cmt

136.83

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2007 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TOM Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2007 5:00 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Tied on the 4 1/2" - pumped 100 sxs cement with 400# hulls - on vacuum - stopped - let set 1/2 hour.  
Pumped 100 sxs cement with 200# hulls - still on vacuum - shut down - waited one hour.  
Pumped 130 sxs cement with 200# hulls - tube full.  
Tied on backside - pumped 20 sxs cement.  
S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
4087	4095		

INVOICED

DATE 12-19-07  
INV. NO. 2008060944

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 12 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #28850.

Plugged through: CSG

District: 04

Signed

*Marvin Mills*  
(TECHNICIAN)


115

DEC 10 2007

*RF*

REPLACEMENT CARD

DON E. PRATT  
P. O. BOX 370 #1-2 ZIEGLER "OWWO" 2-12-25W  
HAYS, KS 67601 C. SE NW  
CONTR RED TIGER DRILLING CO. CTY TREGO  
GEOL \_\_\_\_\_ FIELD HLADEK  
ELV 2572 KB SPD 3/17/84 CARD ISSUED 5/17/84 IP P 15 BOPD, NW  
2569 GL LKC 4087-4095



LOG	Tops .....	Depth/Datum
HEEB	.....	3890-1318
TOR	.....	3914-1342
LKC	.....	3918-1346
BKC	.....	4174-1602
OTD	.....	4200-1628
DDTD	.....	4210-1638
LTD	.....	4213-1641

API 15-195-21,131-A

OLD INFO: OPERATOR WAS BREEZE EXPLORATION, INC., #1-2 ZIEGLER, SPD 12/8/82, SET 8 5/8 " 300, 4 1/2 " 4200, COMP. AS TEMP ABD, (CARD ISSUED 6/16/83), CONTR: H-30 DRILLING, INC.

DST (1) 4080-4100 (LKC) / 15-30-60-120, REC 30' GCM, SIP 107-311#, FP 52-52 / 33-33#

MICT - CO, PF (LKC) INTV NA, ACIDIZED (AMT NA), SWB DWN, NON-COMMERCIAL, TEMP ABD NEW INFO: FR 3/7/84, RE-ENTERED 3/17/84, WSH DWN, SET 4 1/2 " 4200, MICT - CO, PF (LKC) 4087-95, AC 500G (15% SGA), SWB DWN, REC 4.5 BOPH / 2 HRS, RE-AC 2000G (15% SGA), SWB DWN, REC 8.7 BOPH / 2 HRS, T&R, POP (4/27/84), P 24.92 BO & 1 BWPD, 5/2/84, INITIALLY, DECL & STAB AT 15 BOPD, NW

CORRECTION & INFO RELEASED: 9/6/84 - ELEV WAS 2574 KB, ADDED DST INFO