

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20490-00-01
Spot: N2NESE Sec/Twnshp/Rge: 26-9S-32W
2308 feet from S Section Line, 724 feet from E Section Line
Lease Name: HOWARD TRUST Well #: 1-26
County: THOMAS Total Vertical Depth: 4700 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4438	0	w/310 sxs cmt
SURF	8.625	260	0	w/unknown sxs cmt

152.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2007 1:30 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LEON PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: 12/05/2007 - Ordered 270 sxs 60/40 pozmix - 4% gel - 600# hulls.
12/06/2007 - Ordered 250 sxs 60/40 pozmix - 4% gel - 800# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2007 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 260' w/unknown sxs cement.
4 1/2" production casing set at 4438' w/310 sxs cement.
TD 4700'. PBTD 4437'.
Ran tubing to 4250' - pumped 40 barrels of drilling mud - 50 sxs cement with 500# hulls.
Pulled tubing to 1900' - pumped 220 sxs cement with 200# hulls.
Lost circulation. Pulled tubing to surface. Shut down at 7:00 PM.
12/06/2007 8:30AM Tagged cement with tubing to 1200' - pumped 90 sxs cement with 350# hulls.
Cement to surface. Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 15 sxs cement.
Max. P.S.I. 600#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 1/4 barrel water - surface casing leaking.
Called welder for repair.
Connected to 8 5/8" surface casing - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
4254	4330		

INVOICED
DATE 12-19-07
INV. NO. 2008060945

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENT COMPANY-TICKET #147.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RAYMOND OIL COMPANY, INC
WICHITA, KS 67202

26-09 -32W
C N/2 NE SE

#1 HOWARD TRUST

site: 2-1/4 S & 5-1/4 E OF MINGO, KS city: THOMAS API 15-193-20490
contr: MURFIN DRILLING COMPANY #2 field: WC (3/4 W OF OHL SE)
geol: CLARKE SANDBERG

fr spd drlg card last
date 11/20/89 date 11/24/89 comp 12/02/89 issued 12/27/89 revised 12/27/89

ELV: 3046 KB LOG	IP status:
tops.....depth/datum	D&A, MISS, 12/02/89
ANH.....2617 +429	CSG: 8-5/8" 260
B/ANH.....2647 +399	NO CORES
LANS.....4064 -1018	DST (1) 4225-4280 (LANS 180), / 30-45-30-45, REC-240'
STARK.....4274 -1228	MCWO (50% OIL, 45% M, 5% W), 180' OCM (5% OIL,
CHER SH.....4560 -1514	95% M), 180' OCWM (10% OIL, 60% M, 30% W) ISIP
MISS.....4640 -1594	722# FSIP 722# IFP 66# -201# FFP 234# -285# BHT
LTD.....4699 -1653	136 °
RTD.....4700 -1654	DST (2) 4541-4614 (JOHNSON ZN), PKR WOULD NOT
	HOLD, MISRUN
	DST (3) 4224-4268 (LANS 180, W/STR PKR), / 60-60-
	60-60, REC 809' M, W / SCUM OIL (LESS THAN 2% OIL)
	ISIP 730# FSIP 730# IFP 58# -401# FFP 413# -413#
	BHT 128 °

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

STATE	KANS	COUNTY	THOMAS	OWWO	26-9S-32W
FIELD	OHL SW-1/2 MI E PROD (MARMATON)				N2 NE SE
OPER	SHAMROCK RESOURCES				2310FSL .60FEL SEC
WELL	1-26 HOWARD TRUST			WELL CLASS	WOE
API	15-193-20490-0001			STATUS	OIL-WO
SPUD	09/02/1990			COMP	10/31/1990
DTD	4700	LTD		PSTD	4438

+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+
+	+	+	+	+	+

LOC 6 MI SE MINGO, KS

Petroleum Information Corporation

IPP 90 BOPD 80 BW GTY 39 EL: 3046 KB 3041 CR
PROD ZONE: LANSING 4254-4330 GROSS
(LANSING EXTENSION)

CSGS: 4 1/2 @ 4438 W/ 310 SACKS
TBGS: 2 3/8 @ 4293
DRLG COMP 9/6/90 RIG REL 9/6/90

OWWO: OLD INFO: FORMERLY RAYMOND OIL 1 HOWARD TRUST. SPUD 11/24/89. 8 5/8 @ 260 W/CMT. LOG TOPS: LANSING 4064, CHEROKEE 4560, MISS 4640. OTD 4700. COMP 10/2/89. D&A.

NEW: CO TO 4450
PERFS: LANSING PERF 4254-4330 GROSS
4254-4260 4322-4330
ACID 1000 GALS 15% NE 600 GALS 15% MCA

OPER ADDRESS: 100 N MAIN, STE 802, WICHITA, KS 67202
CONTR: J V MALLARD GEOL: KEVIN HOWARD
ID CHANGES: FIELD CHGD FROM OHL