

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20797-00-00
Spot: SWNWSESW Sec/Twnshp/Rge: 23-13S-32W
830 feet from S Section Line, 1519 feet from W Section Line
Lease Name: BADER Well #: 1-23
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226		

152.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/07/2007 6:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2446

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 12/07/2007 9:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2512' w/25 sxs.
2nd. Plug at 1161' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 12-19-07
INV. NO 2008060946

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 12 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN)

DEC 10 2007

PKG