



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

15-065 - 20223-00-00

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 05-26-1969

Dear Sir:

Mr. Lowell Moore of G & G Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Wheeler Well No. 4

Location: CN/2-S/2-SW Sec. 8 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3838' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

186'--8 5/8" Surface casing cement circulated with 150 Sx.
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' w with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Pichler

Conservation Division Agent