



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

15-065-00101-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1974
02-05-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Parsons of D. G. Hansen Trust has this
date requested permission to plug the following described well:

Mr. Parsons guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Muilenburg Well No. 1

Location: SE-NE-SE Sec. 1 Twp. 10 Rge. (E)(W)21

County: Graham Total Depth 3875' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parsons was instructed to plug the well as follows:

194'--8 5/8" Casing, cement circulated with 125 Sx.
3840'--5 1/2" Production casing cemented on bottom with 100 Sx. Open hole
completion, no plug-back nor perforations indicated.

Sand to 3825', and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing
and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement,
staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent