

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-01709-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name: Wheeler Well No. 3

Location: CW/2-W/2-SW Sec. 8 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3858 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

177'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3841'--5 1/2" Production casing cemented with 100 Sx. Dakota section from 950' to 1150'.

Sand well back to 3825' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 20 sacks gel using 5 sacks hulls in initial gel then 100 Sx. cement follow with 14 sacks gel then 20 Sx. cement. Follow with 2 sacks gel and 8 Sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 18 1967
09-18-1967
CONSERVATION DIVISION
Wichita, Kansas
A. L. Nichols
Conservation Division Agent