



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-19118-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas
10-07-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Baker of NCRA has this

date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Copperative Refinery Association

Complete Address: Box #6, Great Bend, Kansas.

Lease Name: Wheeler Well No. 1

Location: SE-NE-SW Sec. 8 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3883' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Baker was instructed to plug the well as follows:

245'--8 5/8" Surface casing, cement circulated.
3882'--5 1/2" Production casing cemented on bottom with 125 Sx. Bridge plug
@ 3822'. Top perforations from 3641' to 3646'. 5 1/2" has been squeezed
thru holes @ 1191' and 1250' with 300 Sx. cement. 5 1/2" now has another
hole at an undetermined depth.

Squeeze well with 1 sack hulls, 75 Sx. cement and 60 sacks gel staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent