

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 195-21993-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____

Well Operator: Bear Petroleum, Inc. KCC License #: 4419
(Owner / Company Name) (Operator's)

Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: (316) 524 - 1225

Lease: Shubert Well #: B1 Sec. 27 Twp. 11 S. R. 22 East West

NE - NE - NW Spot Location / QQQQ County: Trego

4960 4922 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2970 2979 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 250 Cemented with: 180 Sacks

Production Casing Size: 4 1/2" Set at: 3960 Cemented with: 450 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3865-74

Elevation: 2260 (G.L. / K.B.) T.D.: 3960 PBDT: 3960 Anhydrite Depth: 1711

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): According to the rules and regulations of the KCC

**RECEIVED
KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

NOV 27 2007

If not explain why? _____
**CONSERVATION DIVISION
WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: R. A. Schremmer
Bear Petroleum, Inc.

Address: P.O. Box 438 Phone: (316) 524 - 1225
City / State: Haysville, KS 67060

Plugging Contractor: Alliance Well Service, Inc. KCC License #: 33346
(Company Name) (Contractor's)

Address: 271 Lake Rd., Pratt, KS 67124 Phone: (785) 623 - 1066

Proposed Date and Hour of Plugging (if known?): unknown 11-26-07

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 11-26-07 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** well plugged - KCC-Dlg*

*Dist
04*

replacement card

STRATA ENERGY RESOURCES
NEWPORT BEACH, CA 92660

27-11 -22W
NE NE NW

#1 STRATA-SCHUBERT "B"

site: 2-1/2 N & 6-1/2 E OF WAKEENEY, KS	city: TREGO	API 15-195-21993
contr: REVLIN DRILLING	field: SHAW CREEK EXT (1/8 W)	
geol: BETH FUHR		
fr date 08/24/88	spd date 09/15/88	drig comp 09/20/88
	card issued 01/04/89	last revised 05/24/89

ELV: 2260 KB LOG	
tops.....	depth/datum
ANH.....	1711 +549
TOP.....	3288 -1028
HEEB.....	3500 -1240
TOR.....	3524 -1264
LANS.....	3538 -1278
BKC.....	3771 -1511
MARM.....	3856 -1596
ARB.....	3946 -1686
RTD.....	3960 -1700

IP status:
OIL, P 7 BOPD, NW, MARM 3865-3874 ,
CORRECTION & INFO RELEASED: 5/24/89 - WAS D & A -
TIGHT HOLE IN ERROR; ADDED WELL INFO
CSG: 8-5/8" 250 / 180 SX, 4-1/2" 3960 / 450 SX
NO CORES
DST (1) 3860-3895 (MARM), / 30-45-30-60, WB BLDG
TO 2 INCHES, REC 60' HOCM (45% OIL) ISIP 1085#
FSIP 1074# IFP 44# -44# FFP 55# -55# IHP 2177# FHP
2155# BHT 117 °
MICT - CO, PF (MARM) 3865-3874, W / 2 SPF, AC 1500
GAL (15% DS/FE), GSO, SET 2-3/8" TBG AT 3951, POP,
P 7 BOPD, NW (GR 34), 12/17/88

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 27 2007

CONSERVATION DIVISION
WICHITA, KS



BEAR PETROLEUM, INC.

POST OFFICE BOX 438
HAYSVILLE, KANSAS 67060
PHONE: (316) 524-1225
FAX: (316) 524-1027



November 26, 2007

KCC – Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202

RE: Shubert B#2
Trego County, KS

On November 16, 2007, we inadvertently filled out a CP-1 and CDP-1 on the Shubert B#2 well (API # 15-195-21998).

Please disregard the application to plug the well. We are not plugging the B2 well at this time.

Please let me know, if you have any questions.

Yours Truly,

Shannon Howland
Office Manager

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 27 2007

CONSERVATION DIVISION
WICHITA, KS