

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 035-22534 -00 -00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 5-29-80

Well Operator: Ron Whiteman dba/Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd City: Cambridge

State: Kansas Zip Code: 67023 Contact Phone: ( 620 ) 467 - 2615

Lease: Stolp Well #: 10 Sec. 29 Twp. 30 S. R. 7  East  West

SE - NW - NE Spot Location / QQQQ County: Cowley

990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 210 Cemented with: 130 Sacks

Production Casing Size: 4 1/2 Set at: 2928 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs from 2897 to 2904 (MISS)

Elevation: 1475 ( G.L. /  K.B.) T.D.: 2930 PBDT: 2907 Anhydrite Depth: unknown

(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of hole with sand to 50 ft above perfs and dump-bail 6sx cement on top, shoot and pull pipe, for top plug circulate cement from 50 ft below surface pipe or 350 ft to surface

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman (cell # 620-222-4316)

Phone: ( 620 ) 467 - 2615

Address: 8135 281st rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd Phone: ( 620 ) 467 - 2615

Proposed Date and Hour of Plugging (if known?): will call in to district office 12-4-07

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/17/2007 Authorized Operator / Agent: Brent Whiteman (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

\* well plugged - KCC-Dlg

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**NOV 21 2007**  
CONSERVATION DIVISION  
WICHITA, KS


Dist  
02

990 from N Line  
1650 from E Line

STATE	KANSAS	8-4-119	MAP NO.	S-T-R	29-30S-7E	D
OPER	K T WIEDEMANN TRUST			SPOT	SE NW NE	INIT
	BOX 1276 ELDORADO KS 67042			CO	COWLEY	DO
WELL	10 MELVIN STOLP			ELEV	2745 KB	FIN
CONTR	WHITE & ELLIS DRLG				2475	
FIELD	BOX (MISS)					

IP	IPP 8 BOPD + TR WTR, MISS 2897-2904	KB SPL TOPS	
	API 15-035-22534	FR 5-6-80	
	SPUD 5-29-80, 8 5/8@210 w/130, Geol	HOGSHOOTER	2112-367 637
	Paul Koontz	LAYTON	2127-373 652
	RTD 2930, 4 1/2@2928 w/75	KANSAS CITY	2138-384 663
	Perf (MISS) 14/2897-2904, 1500GA	B/KANSAS CITY	2368-623 893
	IPP 8 BOPD + TR WTR, MISS 2897-2904	ALTAMONT	2406-661 931
	COMPLETED 8-11-80	PAWNEE	2460-715 985
		FORT SCOTT	2522-777 1087
		CHEROKEE	2600-855 1125
		MISS CHERT	2880-1135 1405
		MISS DOLO	2896-1151 1421
		RTD	2930-1185 1445
		TD IN MISS	

COMP ISSUED 8-26-80

 Petroleum Information Corporation  
A Subsidiary of A C Nether Company  
©Copyrighted 1980 Reproduction Prohibited

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 21 2007  
CONSERVATION DIVISION  
WICHITA, KS