

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 035-22747 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 1/29/1981

Well Operator: Ron Whiteman dba/Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd City: Cambridge

State: Kansas Zip Code: 67023 Contact Phone: ( 620 ) 467 - 2615

Lease: Stolp Well #: 14 Sec. 29 Twp. 30 S. R. 7  East  West

- NW - SE - NE Spot Location / QQQQ County: Cowley

1650 990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 208 Cemented with: 140 Sacks

Production Casing Size: 4 1/2 Set at: 2906 Cemented with: 50 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs from 2864 to 2870 and 2874 to 2884 (MISS)

Elevation: 1451 ( G.L. /  K.B.) T.D.: 2907 PBD: 2889 Anhydrite Depth: unknown

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of hole with sand to 50 ft above perfs and dump-bail 6sx cement on top, for top plug circulate cement from 350 ft to surface

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 21 2007

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman (cell # 620-222-4316)

Phone: ( 620 ) 467 - 2615

Address: 8135 281st rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd Phone: ( 620 ) 467 - 2615

Proposed Date and Hour of Plugging (if known?): will call in to district office

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/17/2007 Authorized Operator / Agent: Ronnie Whiteman (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MELVIN STOLP #14

Comm. Rotary 1/29/81  
 Comp. Rotary 2/3/81

NW SE NE 29-30S-7E  
 Cowley County  
 Started Pumping 2/26/81

CABLE TOOLS  
 Comm. C.T. 2/19/81  
 Comp. C.T.

CEMENT  
 8 5/8 @ 208' 140 sax cmt. Elev. K.B. 1451'  
 4 1/2 @ 2906' 50 sax cmt. Elev. GL. 1446'

Csg. Record  
 8 5/8 surface 208'  
 4 1/2 csg. 9.5# @ 2906'

ELEVATION (RB)	(+1451)
Hogshooter Limestone	2086 (636)
Layton Sand	2098 (647)
K.C. Limestone	2118 (659)
Base K.C.	2348 (897)
Altamont Limestone	2384 (933)
Pawnee Limestone	2444 (993)
Fort Scott Limestone	2516 (1065)
Cherokee Shale	2580 (1129)
Miss. Chat.	2858 (1407)
R.T.D.	2907 (1456)

2/19/81

White & Ellis moved in and rigged up.

Logged well at 2889'

Perfs. @ 2864-70 2 SPF  
 2874-84 2 SPF

Swabbed well down. Free oil after 30 min.

United Cementing & Acid acidized well w/250 gal. MCA 15%. Breaking pressure 700#  
 Rate 3 BPM. Swabbed acid back. Free oil. Shut down.

2/20/81

Checked fill up. 650' total fluid. 400' oil and 250' water. Partly acid water.

1 hr. test 100'-oil 50'-water

2 hr. test 100'-oil 25'-water

Tore Cable tools down.

2/25/81

Phillips Well Service ran 88 jts. 2 3/8 O.D. EUE 8rd thd tubing w/1-8' & 1-6' tbg. subs.

85 - 5/8x25' sucker rods

29 - 3/4x25' sucker rods

2x1 1/2x8' B.H.D. pump.

3/19/81 Acidized w/1000 gal 15% 2 1/2 x 3 BPM @ 150 to 200 #

RECEIVED  
 KANSAS CORPORATION COMMISSION

NOV 21 2007

CONSERVATION DIVISION



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

WHITEMAN, RON DBA GEN-DOR OIL CO.  
8135 281ST RD  
CAMBRIDGE, KS 67023-9308

December 27, 2007

Re: STOLP #14  
API 15-035-22747-00-00  
29-30S-7E, 990 FSL 990 FEL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after June 24, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000