

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 035-22292 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 12/27/1979

Well Operator: Ron Whiteman dba/Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd City: Cambridge
(Owner / Company Name) (Operator's)

State: Kansas Zip Code: 67023 Contact Phone: (620) 467 - 2615

Lease: Stolp Well #: 9 Sec. 29 Twp. 30 S. R. 7 East West

- SW - NE - NE Spot Location / QQQQ County: Cowley

990 4290 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 214 Cemented with: 85 Sacks

Production Casing Size: 4 1/2 Set at: 2903 Cemented with: 50 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs from 2870 to 2878 and 2882 to 2892 (MISS)

Elevation: 1462 (G.L. / K.B.) T.D.: 2905 PBTD: 290? Anhydrite Depth: unknown
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of hole with sand to 50 ft above perfs and dump-bail 6sx cement on top, for top plug circulate cement from 350 ft to surface

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

NOV 21 2007

If not explain why? _____

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman (cell # 620-222-4316)

Phone: (620) 467 - 2615

Address: 8135 281st rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576
(Company Name) (Contractor's)

Address: 8135 281st rd Phone: (620) 467 - 2615

Proposed Date and Hour of Plugging (if known?): will call in to district office

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/17/2007 Authorized Operator / Agent: Brent Whiteman
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MELVIN STOLP #9

Comm. Rotary 12/27/79
 Comp. Rotary 1/2/80
 Total Depth 2905'

Sec. 29-30S-7E
 Cowley County

Cable Tools
 Comm. C.T. 1/4/80
 Comp. C.T. 1/9/80

Cement
 8 5/8" Surface pipe w/85 sax
 4 1/2" oil string w/50 sax

Elev. K.B. 1462'
 Elev. G.L. 1457'

Casing Record

8 5/8 Surface 214'
 4 1/2 casing 2903' 9.5# Reg 3 Seamless

Tops @		
Elevation KB		(+1462)
Layton Sand	2108	(- 646)
K.C. Limestone	2115	(- 653)
Base Kansas City	2353	(- 890)
Altamond Limestone	2392	(- 930)
Pawnee Limestone	2448	(- 986)
Fort Scott	2525	(-1063)
Mississippi Lime	2861	(-1399)
Mississippi Dolomite	2878	(-1416)
R.T.D.	2905	(-1443)

Log - 2870?

DRILLING-IN-DATA

Perfs 2870 - 78
 2882 - 2892

1/4/80
 Moved to Location

1/5/80
 Rigged up. Strung up 4" tools, Swab casing to 2400'

1/7/80
 Logged well. Drilled out 11' cement. Set Bridge plug @ 2898'.
 Perf. well @ 2870'-2878' 5 shots
 2882'-2892' 6 shots
 Swab hole dry. Last pull show of oil.

RECEIVED
 KANSAS CORPORATION COMMISSION

NOV 21 2007

CONSERVATION DIVISION
 WICHITA, KS

1/8/80
 490' fluid in hole. 280' clean gassy oil - 210' water
 Swab testing
 1 hr. 90' fluid 50' oil 40' oil & water
 2 hrs. 90' " 70' " 20' " " "
 2 hrs. 90' " 70' " 20' " " "
 2 hrs. 90' " 70' " 20' " " "

97
 1100
 63
 70

1/9/80
 550' fluid in hole. Ran 89 jts. 2 3/8 O.D. EUE 8rd thd tbg (new) - 25' mud anchor - 2' Perfs. - 1' SN - 1-8' - 1-6' 1-2' tbg subs
 113 3/4 x 25' sucker rods (new) 1-6' 1-8' peng rods, w/2 x 1 1/2 x 6' THD pump

1/22/80
 Acidized well w/1000 gal. 15% N.E. Acid. Broke @ 500# injection. 3 1/2 bbl. min. @ 300# on vaccum after complete overflushed w/29 bbls.



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WHITEMAN, RON DBA GEN-DOR OIL CO.
8135 281ST RD
CAMBRIDGE, KS 67023-9308

December 27, 2007

Re: MELVIN STOLP #9
API 15-035-22292-00-00
29-30S-7E, 4290 FSL 990 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 24, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000