

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: SWD Docket #: D-21,084
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/07/2007 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 4128' Bottom: 4191' T.D. 4191'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 195-21992-0001
Lease Name: Huffman
Well Number: 3 SWD
Spot Location (QQQQ): approx S1/2 S1/2 SW
330 Feet from North / South Section Line
1170 Feet from East / West Section Line
Sec. 2 Twp. 12 S. R. 22 East West
County: Trego
Date Well Completed: 05/04/1982
Plugging Commenced: 12/07/2007
Plugging Completed: 12/07/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Water	4128'	4191'	8.625"	217'	-0-
				4.50"	4128'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 2490'. Pumped 110 sx 60/40 Pozmix w/ 4% gel + 250 hulls. Pulled tubing up to 1350'.
Pumped 35 sx 60/40 Pozmix w/ 4% gel + 150 hulls down tubing. Pulled tubing out of hole. Loaded 4.50" casing w/ 20 sx 60/40 Pozmix w/ 4% gel + 100 hulls. Shut in at 350#. Pumped 30 sx 60/40 Pozmix w/ 4% gel + 100 hulls down 8.625 casing.

Plugging complete at 1:00 p.m. witnessed and approved by Marvin Mills with the KCC

Name of Plugging Contractor: Express Well Service & Supply Inc License #: 6426
Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc. DEC 20 2007

State of Kansas County, Sedgwick, ss. CONSERVATION DIVISION WICHITA, KS

Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN to before me this 19th day of December, 20 07

[Signature] My Commission Expires: 5-4-11
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

