

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: (620)629-4200 Operator License #: 5447
Type of Well: ENHR Docket #: E28,031
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-13-07 (Date)
by: Mike Meier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
N/A Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-081-21317-00-01
Lease Name: Frey Morrow Unit
Well Number: 501 W
Spot Location (QQQQ): _____ - SE - NW - NE
815 Feet from North / South Section Line
1666 Feet from East / West Section Line
Sec. 36 Twp. 27 S. R. 34 East West
County: Haskell
Date Well Completed: 6-6-00 *original*
Plugging Commenced: 11-12-07
Plugging Completed: 11-14-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1755	—
				5 1/2	5480	1820

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls & 25 sx cmt to plug lower perms from 5206 to 5006, pull 2 7/8 to 4170 & mixed 400 lb. hulls & 25 sx cmt to plug upper perms from 4170 to 3970. Shot & pull 5 1/2 to 1785. Circ. hole w/ mud & mixed 50 sx cmt. 1785 to 1635, 40 sx 800 to 680 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. PO Box 2528 Liberal, KS. 1701 N Kansas. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION

(Signature) Kenny Andrews

(Address) 1701 N Kansas PO Box 2528 Liberal, KS. 67905

DEC 20 2007

CONSERVATION DIVISION
WICHITA, KS

SUBSCRIBED and SWORN TO before me this 19 day of Dec. 2007

Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009

KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202