

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: White & Ellis Drilling Inc.
Address: P.O. Box 48848
Phone: (316) 321-0550 Operator License #: 5420
Type of Well: OIL/GAS KCC PRT Per Dallas Flowers Docket #: NA
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-26-07 (Date)
by: Steve Durant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 5082 Bottom: 5108 T.D. 5200
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-20854 -00-00
Lease Name: Thompson
Well Number: 1-8
Spot Location (QQQQ): C - SE - SE -
330 706 Feet from North / South Section Line
330 645 Feet from East / West Section Line
Sec. 8 Twp. 31 S. R. 18 East West
County: Comanche
Date Well Completed: 7-6-92 KCC PRT
Plugging Commenced: 9-26-07 PERCP 2/3
Plugging Completed: 9-27-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	318'	8 5/8	318'	0
Mississippi		5082	5108	4 1/2	5199	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

C1BP set @ 5033 dumped 2x cmt on tap off plug. Perforated casing from 1000' to 1000 1/2' with 2 shots. PU RIHW/ 1020' tbg. Squeezed w/ 70 sx 60/40 poss mix 4% gel. POHW/ tbg. Perforated @ 330' to 330 1/2' w/ 2 shots. Pumped 280 sx 60/40 poss mix 4% gel
Circulated cmt to surface .

Name of Plugging Contractor: Cheyenne Well Service License #: 6454 **RECEIVED**
Address: P.O. Box 384 Ness City, KS 67560 **KANSAS CORPORATION COMMISSION**

Name of Party Responsible for Plugging Fees: White & Ellis Drilling Inc. **DEC 19 2007**
State of KS County, Sedgwick, ss. **CONSERVATION DIVISION WICHITA, KS**
Dallas Flowers (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RHONDA L. MOSIMAN (Signature) [Signature]
NOTARY PUBLIC (Address) _____
STATE OF KANSAS

WV APPT. EXPIRES 2/21/10 SUBSCRIBED and SWORN TO before me this 18 day of Dec, 2007
[Signature] My Commission Expires: 2/21/10
Notary Public