

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil *KCCPPT per CP2/3* Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/27/2007 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LKC Depth to Top: 4068' Bottom: 4074' T.D. 4160'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-21424-00-00
Lease Name: Schimkowitsch CP
Well Number: 2-1 *SW*
Spot Location (QQQQ): SE - NW - NW - SW
2200 Feet from North / South Section Line
440 Feet from East / West Section Line
Sec. 1 Twp. 12 S. R. 25 East West
County: Trego
Date Well Completed: 02/09/1984
Plugging Commenced: 11/23/2007
Plugging Completed: 11/27/2007

KCCPPT per CP2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Water	4068'	4074'	8.625"	261'	-0-
				5.50"	4158'	-0-


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 2850'. Pumped 90 sx 60/40 Pozmix w/ 4% gel + 300 hulls. Pulled tubing up to 1850'.
Pumped 90 sx 60/40 Pozmix w/ 4% gel + 300 hulls. Pulled tubing up to 950'. Pumped 110 sx 60/40 Pozmix w/ 4% gel + 100 hulls.
Pulled tubing out of hole. Topped off 5.50" casing with 140 sx 60/40 Pozmix w/ 4% gel to surface. Pumped 5 sx 60/40 Pozmix w/ 4% gel down 8.625 casing. Shut in at 200#. Plugging complete at 6:15 p.m. witnessed and approved by Marvin Mills with the KCC

Name of Plugging Contractor: Allied Cementing Express Well Service & Supply Inc. License #: 6426
Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.

Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) 
(Address) P. O. Box 783188 Wichita, KS 67278-3188

KCCPPT per CP2/3

SUBSCRIBED and SWORN TO before me this 10th day of December, 20 07

Notary Public _____ My Commission Expires: _____ RECEIVED KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DEC 11 2007

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

28784

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Outlets KS

11-27-07	SEC. 1	TWP. 12S	RANGE 25W	CALLED OUT	ON LOCATION 12:45pm	JOB START 6:00pm	JOB FINISH 6:30pm
DATE							
Schminkowitsch	WELL# CP-2		LOCATION Uda Rd + E70 W.		COUNTY Trego	STATE KS	
LEASE							
OLD OR NEW (Circle one)		New 40 2w - 11w - 11w 6 S					

CONTRACTOR Gyress Well Service OWNER Same

TYPE OF JOB <u>AWP</u>	CEMENT
HOLE SIZE _____ T.D. _____	AMOUNT ORDERED <u>450 60/40</u>
CASING SIZE <u>5 1/2</u> DEPTH _____	<u>40 gal 600 hulls</u>
TUBING SIZE <u>2 3/8</u> DEPTH _____	<u>used 435 sks → 600 hulls</u>
DRILL PIPE _____ DEPTH _____	
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>261 @ 12.60 3288.60</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>174 @ 6.50 1137.00</u>
CEMENT LEFT IN CSG. _____	GEL <u>15 @ 16.65 249.75</u>
PERFS. _____	CHLORIDE @ _____
DISPLACEMENT _____	ASC @ _____

EQUIPMENT		Hulls <u>12 sks @ 25.50 306.00</u>
PUMP TRUCK CEMENTER <u>Fuzzy</u>	# <u>477</u> HELPER <u>Wayne</u>	
BULK TRUCK	# <u>399</u> DRIVER <u>Louie</u>	
BULK TRUCK	# <u>394</u> DRIVER <u>Kelly</u>	
	HANDLING <u>481 @ 1.90 913.90</u>	
	MILEAGE <u>9.25 @ 22.70 207.88</u>	
	TOTAL <u>7949.77</u>	

REMARKS: 90 sks @ 29.45
90 sks @ 19.00
circulate cement to sand @ 1000'
Hookup sledge & pump 115 sks
Top of 5 1/2 with 25 sks
Hookup to backside & pump
5 sks → shut in @ 200'
Job complete @ 6:30pm
(in 4 hrs Fuzzy)

SERVICE	
DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>365.00</u>
EXTRA FOOTAGE @ _____	
MILEAGE @ _____	<u>NA</u>
MANIFOLD @ _____	
TOTAL <u>365.00</u>	

CHARGE TO: Ritchie Exploration

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Thomas A. [Signature]

PLUG & FLOAT EQUIPMENT	
_____ @ _____	
_____ @ _____	
_____ @ _____	
_____ @ _____	
TOTAL _____	
TAX _____	
TOTAL CHARGE _____	
DISCOUNT _____ IF PAID IN 30 DAYS	

PRINTED NAME _____

RECEIVED
 KANSAS CORPORATION
 DEC 11 2007
 CONSERVATION DIVISION
 WICHITA, KS