

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21722-00-00
Spot: SWNENE Sec/Twnshp/Rge: 4-26S-32W
1250 feet from N Section Line, 1250 feet from E Section Line
Lease Name: HEIMAN GAS UNIT Well #: 2 HI
County: FINNEY Total Vertical Depth: 2810 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2807	0	WITH 550 SX CMT
SURF	8.625	997		WITH 450 SX CMT

91.33

Well Type: HI UIC Docket No: _____ Date/Time to Plug: 12/03/2007 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: PUMP 195 SX CMT TO FILL 4 1/2" CASING FROM PERFS TO GROUND LEVEL. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2007 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 223 SX CMT & 200# HULLS DOWN 4 1/2" CASING. PRESSURE TO 250#. PUMP 10 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2600	2634		

INVOICED
DATE 1-2-08
INV. NO. 2008060993

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 27 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS C CMT & 2% GEL BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED
DEC 18 2007
KCC Dodge City

Signed [Signature]
(TECHNICIAN) [Signature]