

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22066-00-01
Spot: SEWNNE Sec/Twnshp/Rge: 2-34S-11W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: SPICER A Well #: 2 OWWO
County: BARBER Total Vertical Depth: 668 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 439

35.00

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 09/06/2007 1:00 PM
Plug Co. License No.: 33902 Plug Co. Name: HARDT DRILLING LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 660' WITH 80 SX CMT. 2ND PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/03/2007 11:15 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

GOT OUT OF HOLE AT 665'. 9/6/07: 1ST PLUG AT 660' WITH 80 SX CMT. 2ND PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE. 12/3/07: **GAS BUBBLING UP AT SURFACE** 1ST PLUG RAN TUBING TO 430' & SPOT 50 SX ASC W/2% CC. 2ND PLUG PULL TO 60' & PUMP 20 SX CMT. THE PLUGGING ON 12/3/07 WAS WITNESSED BY STEVE DURRANT.

Perfs:

INVOICED
DATE 12-19-07
INV. NO. 2008060952

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 11 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
DEC - 4 2007
KCC Dodge City

Signed Steve Durrant
(TECHNICIAN)

PKT