

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20679-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 1-19S-31W
2300 feet from S Section Line, 1825 feet from E Section Line
Lease Name: SCHMIDT Well #: 1-1
County: SCOTT Total Vertical Depth: 4657 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 150 N MAIN STE 801
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 298 | | WITH 210 SX CMT |

151.35

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/12/2007 8:00 AM
Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.
Proposal Rcvd. from: NACHO Company: ABERCROMBIE Phone: (620) 786-4025

Proposed Plugging Method: 1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: NONE
Date/Time Plugging Completed: 12/12/2007 10:30 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

INVOICED
DATE 1-2-08
INV. NO. 2008060991

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 21 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed _____

[Signature]
(TECHNICIAN)

[Handwritten initials]