

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20792-00-00
Spot: SE Sec/Twnshp/Rge: 2-17S-40W
1200 feet from S Section Line, 1200 feet from E Section Line
Lease Name: ADAMS Well #: 4-2
County: GREELEY Total Vertical Depth: 3005 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------------------------|
| PROD | 4.5 | 3005 | 0 | WITH 650 SX CMT |
| SURF | 8.625 | 272 | | WITH 175 SX CMT 97.66 |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2007 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: _____ Phone: (620) 376-8190

Proposed Plugging Method: PUMP 300# HULLS & 195 SX CMT DOWN 4 1/2". PUMP 60 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2007 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2985' TO 0' USING 300# HULLS & 173 SX CMT.
PRESSURE TO 400# & HELD. PUMP 2 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS.
PRESSURE TO 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2972 | 2985 | | |
| 2963 | 2968 | | |

INVOICED
DATE: 1-2-08
INV. NO. 2008061002

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 27 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed _____

Ken Jehlik
(TECHNICIAN)

Form CR-3/3

PJT