

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20794-00-00
Spot: SW Sec/Twnshp/Rge: 11-17S-40W
1250 feet from S Section Line, 1320 feet from W Section Line
Lease Name: HOPPE Well #: 2-11
County: GREELEY Total Vertical Depth: 3007 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3007	0	WITH 600 SX CMT
SURF	8.625	278		WITH 175 SX CMT

97.73

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2007 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: _____ Phone: (620) 376-8190

Proposed Plugging Method: PUMP 400# HULLS & 195 SX CMT DOWN 4 1/2" CASING. PUMP 20 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2007 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2977' TO 0' USING 400# HULLS AND 178 SX CMT. PRESSURE TO 400# & HELD. PUMP 2 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
2965	2977		
2650	2662		

INVOICED
DATE 1-2-08
INV. NO. 2008061002

RECEIVED
KANSAS CORPORATION COMMISSION


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

DEC 27 2007

Plugged through: CSG

CONSERVATION DIVISION
WICHITA KS

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

PKT
Form CP-2/3
PKT