

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21221-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 23-30S-34W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: HOFFMAN Well #: 2-223
County: HASKELL Total Vertical Depth: 5600 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5598	1780	WITH 270 SX CMT
SURF	8.625	1680		WITH 700 SX CMT

182.00

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/18/2007 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRANDON SIROKY Company: OIL PRODUCERS Phone: (316) 682-3022

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 800' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2007 4:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 50 SX CMT. 1ST PLUG AT 1780' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 800' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5507	5511		
5398	5402		
5218	5236		
4738	4748		

INVOICED
DATE 1-2-08
INV. NO. 2008061004

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 27 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS A CMT W/4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

PLS
Form CP-2/3