

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22061-00-00
Spot: SESW Sec/Twnshp/Rge: 17-19S-28W
780 feet from S Section Line, 1820 feet from W Section Line
Lease Name: HELEN Well #: 2
County: LANE Total Vertical Depth: 4720 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		

153.40

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/16/2007 2:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK ROME Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 12/16/2007 4:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 1-2-08
INV. NO. 2008061007

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 27 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

PKS