

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20906-00-02  
Spot: NWNWSW Sec/Twnshp/Rge: 30-30S-40W  
2318 feet from S Section Line, 4685 feet from E Section Line  
Lease Name: NAIRN A Well #: 1  
County: STANTON Total Vertical Depth: 5529 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2310		
CIBP		5295		
CIBP		5386		
DVT		2587		WITH 385 SX CMT
PROD 4.5		5517	0	WITH 200 SX CMT
SURF 8.625		1594		WITH 550 SX CMT

179.69

Well Type: SWD UIC Docket No: D28157.0 Date/Time to Plug: 12/06/2007 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PLUGGING PROPOSAL SAME ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2007 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS TO 2252'. PRESSURE TO 500#. HELD AT 250#. PERFORATE AT 565'. CIRCULATE CMT FROM 565' TO 0' LEAVING 4 1/2" CASING AND 4 1/2" X 8 5/8" ANNULUS FULL WITH 145 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5374	5380		SQUEEZED
5372	5378		
5365	5368		SQUEEZED
5314	5318		
5292	5296		SQUEEZED
2250	2252		


INVOICED  
DATE 1-2-08  
INV. NO. 2008061008

RECEIVED  
KANSAS CORPORATION COMMISSION  
**DEC 27 2007**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: CSG

District: 01



Signed [Signature]  
(TECHNICIAN)