

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05483-00-00

Spot: NW

Sec/Twnshp/Rge: 36-13S-15W

~~4524~~ ~~3960~~ feet from S Section Line,

~~3960~~ feet from E Section Line

Lease Name: DILLNER

~~4095~~ Well #: 2

County: RUSSELL

Total Vertical Depth: 3346 feet

KCC 919
Per
GPS

Operator License No.: 32325

Op Name: POPP OPERATING, INC.

Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3345		150 SX

108.75

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/06/2007 4:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: RICKEY POPP

Company: POPP OPERATING, INC.

Phone: (620) 786-5514

Proposed
Plugging
Method:

[Empty box for Proposed Plugging Method]

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/06/2007 6:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran in with tubing to clear hole. Hit multiple bridges. Washed through with power swivel.
Hit hard at 2120'. Not making hole. Loosing fluid. POOH.
Perf. At 1500' - 850' - 200'.
Ran tubing to 2100' - pumped 80 sxs 60/40 pozmix - 4% gel cement.
Pulled to 1000' - circulated with 100 sxs cement.
POOH. Tied onto casing and pumped 90 sxs cement with 400# hulls.
No surface pipe.
Well apparently had 4 1/2" liner cemented in.

Perfs:

Top	Bot	Thru	Comments
3304	3308		ARB
3227	3231		L-KC

INVOICED
DATE 1-2-08
INV. NO. 2008061009

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING. 38.88350 - 98.94225.

Plugged through: TBG

District: 04

17D

Signed

Case Morris

(TECHNICIAN)

PT

DEC 18 2007

STEARNS PETROLEUM

#2

DILLNER

36-13-15W
C NW

33

Contr.

RUSSELL

Count

E 1879

Comm.

Comp.

2-16-51 IP 75 BOPD

Tops	Depth	Datum
ANH	917	+ 962
HEEB	2987	-1108
LANS	3042	-1163
ARB	3299	-1420
T.D.	3346	-1467

Casing

5" 3346 PERF 3303-11
ACID 1000
600' 01H/14 HRS

GORHAM POOL

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS