

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19174-00-01

Spot: N2NWNW

Sec/Twnshp/Rge: 36-13S-15W

330 feet from N Section Line,

660 feet from W Section Line

Lease Name: PATTERSON (DILLNER)

Well #: 3 TWIN

County: RUSSELL

Total Vertical Depth: 3347 feet

Operator License No.: 32325

Op Name: POPP OPERATING, INC.

Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

CIBP		3030		
------	--	------	--	--

CIBP		3266		
------	--	------	--	--

CIBP		3320		
------	--	------	--	--

PROD	5.5	3347	0	125 SX
------	-----	------	---	--------

SURF	0	0	0	0
------	---	---	---	---

108.78

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/06/2007 2:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: RICKEY POPP

Company: POPP OPERATING, INC.

Phone: (620) 786-5514

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/06/2007 3:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 320 sxs 60/40 pozmix - 4% gel cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
No surface pipe.
Well was DV'd (cemented) from 940' to surface.

Perfs:

Top	Bot	Thru	Comments
3329	3331		ARB
3303	3306		ARB
3203	3209		L-KC
3129	3133		L-KC
3084	3088		L-KC
3068	3071		L-KC
3044	3048		L-KC
2952	2958		L-KC
2871	2875		TOPEKA
2763	2766		TOPEKA

INVOICED

DATE 1-2-08

INV. NO. 2008061009

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING. 38.88452 - -098.94453.

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

DEC 18 2007

36-13-15W
 SE NW NW NW
 BARTON BROTHERS #3 DILLNER
 Contr. V D SIDEY RUSSELL County
 E 1884 RB Comm. 6-26-60 Comp. 8-19-60 IP 25 BOPD

Tops	Depth	Datum
ANH	930	+954
GRANDHAVEN LM	2432	-548
1ST TARK SND	2444	-560
DOVER LM	2465	-581
LANGDON SH	2472	-588
TARK LM	2507	-623
WILLARD SH	2527	-643
ELMONT LM	2563	-679
TOP	2701	-817
HEEB	2990	-1106
LANS	3045	-1161
ARB	3298	-1414


TD 3348 -1464
 INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

Casing

5" 3347

PERF 3325-29: ACID 500: SQZ:
 PERF 3327-29: ACID 500: PERF
 3299-3301

GORHAM POOL



BILL RICHARDS, GEO.