

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-00947-00-00

01-10-1969
RECEIVED
CORPORATION COMMISSION
JAN 10 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robert L. Austin

Complete Address: P. O. Box 159 Stafford, Kansas 67578

Lease Name Eliza Well No. 1

Location W/2 NE Sec. 26 Twp. 10 Rge. 20 (E) (W) XX

County Rooks Total Depth 3796

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling, Inc.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2P Day 9 Month 1 Year 1969

The Above well was plugged as follows:

Total Depth 3796' 8 5/8 csg set at 270' cwc

5 1/2 csg set at 3788' cw 100 sc cmt.

5 1/2 csg squeezed (0-9000) W/400 sc cmt.

No pipe recovered.

Filled 5 1/2 csg with sand (3770-3796) dumped 5 sc cmt W/dump bailer. (3730-3770)

Mud to 650' set rock bridge (635-650)

Filled to surface with 4 yds readymix cmt. (635-0)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 1/10/69
INV. NO. 9170-4