

DISTRICT CONSERVATION AGENT'S REPORT

TO: 15-163-03157-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 25-2
LOCATION SE SE NE
SEC. 26 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Eliza

Operator Morganstern & Specter Address Russell, Kans

Field _____ County Rooks

Total Depth 3749 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" 1609' circulated with 610 sax cement - 5 1/2" at 3747' with
100 sax cement behind.

Filled with chat to 3737' set 5 sax cement with dump bailer, pulled
3057' 5 1/2" - circulated hole with heavy mud through 5 1/2" - (25 sax Gel)
pumped 35 sax cement through 5 1/2" at 550', heavy mud to 35', set
rock bridge and 10 sax cement to bottom cellar.

District Conservation Agent

Date 7-20-57

PLUGGED
FILE SEC. 26 TWP. 10 RGE. 20W
BOOK PAGE 25 L. 2

RECEIVED
STATE CORPORATION COMMISSION
07-02-1957
JUL 24 1957
CONSERVATION DIVISION
Wichita, Kansas