

15-163-19367-00-00

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE SW SW

SEC. 26 TWP. 10 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. R-1 Lease Armbruster "B"

Operator Cities Service Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3860 Feet.

Plugging Contractor Glen Peel Drg Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 200' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 600', displaced 20 sax cement through drill pipe, set cementing plug at 240', displaced 20 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

District Conservation Agent

Date

9-22-57

09-24-1957

CC. CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 26 T 10 R 20W
BOOK PAGE 48 LINE 20